

PETRA III Operation & PETRA IV Status

ESLS Workshop 2025

SOLEIL, 30.10.2025

Michaela Schaumann


on behalf of the PETRA III Operations Team

PETRA III Operations Team: J. Keil, G. Sahoo, M. Schaumann, R. Wanzenberg

PETRA IV Project Team: R. Bartolini, H. Reichert et al.

HELMHOLTZ





24 Beamlines are in operation
+ 1 in commissioning
+ 1 in preparation

*More than 50 experiments covering
most relevant methods*

The world's biggest storage ring light source

Parameter	PETRA III
Energy / GeV	6
Circumference /m	2304
Emittance (horz. / vert.) /nm	1.3 / 0.013
Number of bunches	40 or 480
Total current / mA	100 or 120

Content

PETRA III Operation in 2025

Plans for the Long Shutdown from Sept. 2026

Status of the PETRA IV Project

4656 user hours are scheduled for 2025


Two-week “operable” period in December to support energy management at DESY

	January 2025	February 2025	March 2025	April 2025	May 2025	June 2025	July 2025	August 2025	September 2025	October 2025	November 2025	December 2025			
1	New Year	A	tr	40 Hercules	multi laborDay β	multi	1	multi	A	40	multi	tr	40	1	
2	A	A	tr	40 Hercules	multi β	multi	2	A	A	40	multi	tr	40	2	
3	A	IMV	tr	40 Hercules	multi β	multi	3	multi	A	multi Reunif day	tr	A	3		
4	A	IMV, NG	40	40 Hercules	multi β	A	4	multi	A	40	multi	40	multi	4	
5	A	NG	40	40	multi β	A	5	multi	A	40	multi	40	multi	5	
6	A Wiggler	IM	40	40	multi β	A	6	multi	A	40	multi	40	multi	6	
7	A	IM	40	40	A β Tours M		7	multi	A	40	multi	40	multi	7	
8	A		40	40	multi β	Pentecos	8	multi	A	40	A β	40	multi	8	
9	A		40		multi β	Pentecos	9		A	40	multi β	40	multi	9	
10	A	NG IEV MvL	40	40	multi β	IB tr	10	multi	A	A	40	multi β	40	multi	10
11	A	NG IE MvL	40	40	multi β	tr	11	multi	IB	40	multi β	40	multi	11	
12	A	NG IE MvL	A	40	multi β	multi	12	multi	IB	40	multi β			12	
13	A Wiggler	NG IE MvL	40	40	multi β	multi	13	multi	PETRA IV	40	multi β	40	operable	13	
14	A	NG	40	A	β	multi	14	multi	Studies	40	multi β	40	operable	14	
15	A		40	A	multi β	multi	15	multi		40	β	40	operable	15	
16	A		40	A	multi β	multi	16	multi		40	multi β	40	operable	16	
17	A	IE PXN	40	A	multi β	multi	17	multi		40	multi β	40	operable	17	
18	A	IE PXE	40	Good Fr	multi β	multi	18	multi	IB AU-UHH	40	multi β	40	operable	18	
19	A	IB			multi β	multi	19	multi	IB AU-UHH	40	multi β	A	operable	19	
20	A IEV	IB, IL Reserve	40	Easter Su	multi β	multi	20	multi	IB TR AU-UHH	40	multi β	40	operable	20	
21	A IEV	IB	40	Easter Mo	A	multi	21	A	tr AU-UHH	40	multi β	40	operable	21	
22	A		40	IB tr β	multi	multi	22	A	tr AU-UHH	A	multi β	40	operable	22	
23	A		40	tr β	multi	PETRA IV	23	A	tr	TODAY	40			23	
24	A	IB	40	multi β	multi	Studies	24	A	tr	multi β	40			24	
25	A	IB	40	multi β	multi		25	A	40	IB works out	multi β	40	Xmax	25	
26	A	IB	A	multi β	multi	multi	26	A	40	IB tr	multi β	40	Xmas	26	
27	A Wiggler	IB	40	multi β	multi	multi	27	A	40	tr	A ev P02.1	40		27	
28	A	IB tr	40	multi β	multi	multi	28	A	40	tr	A undulator	40		28	
29	A IEV		40	multi β	multi Ascension	multi	29	A	40	A	40			29	
30	A		40	multi β	multi	multi	30	A	40	IB tr	40			30	
31	A		40 Hercules		multi		31	A	40	tr Reformat.		Booom		31	

Shutdown
 Studies / Machine Development
 Test Run
 User Run

Already delivered 75% of user time scheduled for 2025 with 98.2% availability


MTBF of ~65h thanks to low general fault rate – in total 54 faults during user run



	Done	Target
Availability	98.2%	98%
MTBF	65 h	60 h
MTTR	1.2 h	-

Stable availability around 98%

Major source of faults in 2025 were issues around the cooling water infrastructure



KW20/23/24

→ 3 punctured water hoses of the same type

KW27


→ defect water filter polluted cooling water system around the whole ring

KW37

→ radiation damaged temperature sensor caused frequent beam dumps

Series of broken water hoses – faster ageing due to higher water temperature

Water hoses on a particular position at all sextupoles in the copper-water circuit have been exchanged



- 3x water leaks during user run
- **All hoses** of this position **exchanged** during summer shutdown
 - *Most found to have the same symptoms*
- Sextupoles of SCu type are operated at higher current
 - higher water temperature
 - higher stress on material
- **Samples of other locations** on “hose tree” of SCu and SAI show **good condition**.



Inside covered by copper rust, point-like holes and cracked defects



Always same piece of hose connecting the sextupole coils to the Cu-water circuit.

Broken water filter distributed resin particles over the full copper-water circuit

529 dirt traps had to be cleaned before machine operation could continue



Cleaning of all dirt traps in the tunnel and the power supplies that are connected to the Cu water circuit.



Installation of dirt traps on connections to filter.


Filter exchanged.
Root cause analysis showed that mesh keeping the particles inside the filter had detached.



Triggered further discussions on dirt trap concept for PETRA IV

First light from PU25 undulator

The commissioning of the PU25 Undulator is finished – Beamline P25 is getting ready for first light



Partnership of industry and DESY
Innovation and Technology Transfer (ITT)
& Photon Science


Beamline for Applied Bio-Medical Imaging,
Powder Diffraction and Innovation



Optics Hutch 1:
P25 Double Crystal
Monochromator (DCM)




Optics Hutch 2:
White- and mono-beam test
station



Approved schedule for 2026 with long shutdown and 3144 h user run

Many external boundary conditions influenced the scheduling



Main tasks during the shutdown:

- Campus west: 110kV cable works
- PIA renovation
- Interlock renovation LINAC, DESY, PETRA
- Urgent renovations in PETRA complex – mainly injectors
- Wiggler section realignment
- Re-routing of cables in PETRA North (prep. for PETRA IV)

Shutdown Studies / Machine Development Test Run User Run



PIA refurbishment in long shutdown from Sept. 2026

Project long due, but delayed due to delivery issues



Core items to be renewed

- New **sextupoles** and **quadrupoles**
- **Dipoles** will be equipped with new coils
- New **BPM electronics**
- New **vacuum chambers**
- General refurbishment of the **hall**



Refurbishment of the interlock system from Sept. 2026

Ensure continued safe operation of the PETRA III complex in compliance with current standards

Key safety components reach end of 20-year mission time in 2027

- Demand to continue operation of PETRA III and the pre-accelerators until 2029
- The **personnel safety systems (PSS)** at **LINAC II**, **DESY II** and **RF safety interlock** at **PETRA III** will undergo a **comprehensive refurbishment**.



Safety Interlock System

Ensuring fast switching off of the hazard source (electron beam, RF) in emergency situations.



PETRA IV.

NEW DIMENSIONS



High-energy x-rays will be up to 800x brighter than at PETRA III

PETRA IV will run with round beams in full coupling operation



Photon source size – ideal imaging capabilities

Standard operation: *full coupling*

12	x	12	(pm-rad)²	emittance
5	x	5	µm²	source size
2.4	x	2.4	µrad²	source divergence

PETRA IV brightness mode


1900 bunches , 4 ns spacing, 200 mA (1 nC per bunch)

PETRA IV brightness at 100 keV
higher than for 10 keV at PETRA III today!!

A new accelerator complex in an extended & refurbished infrastructure



Project pillars are the civil construction, accelerator complex and experimental facilities

Civil Construction and Infrastructure




- > Demolition of 28 buildings
- > Construction of 49 buildings/structures
- > Refurbishment of 11 buildings
- > Extended/advanced technical infrastructure


Accelerator Complex



Experimental Facilities



- > 31 new photon beamlines
- > 60 new/refurb. endstations
- > 62 new/refurb. laboratories




Project timeline fixed by (external) boundary conditions

July 2025: PETRA IV was classified as "Research Infrastructure of National Importance"





PETRA IV put on roadmap
priority list for large-scale
research infrastructures in
Germany



Fully symmetric 8-fold H6BA cell structure with 72 cells over 2.3km

Dynamic aperture sufficient for off axis injection (~8mm with errors - 6mm at injection point)

Momentum aperture sufficient for beam lifetime >10h (brightness mode)



Prototypes for the main critical components are on site


A mock-up girder is being assembled with prototypes and dummy magnets




corrector




Sextupole



Climatic cabin for magnetic measurements



DLQ



RF: 500 MHz



RF: 3rd HC




Vacuum chamber for mock up girder

Mock-up girder is been assembled with prototypes and dummy magnets

Prototype girder is now in the testing phase

Magnets, vacuum equipment, diagnostics will be assembled, aligned and tested on girders





PETRA IV will have 288 girders



Injector baseline: construction of a new booster - DESY IV


with lower emittance than the existing DESY II (from 335 nm to 20 nm)



Laser Plasma Accelerator (LPA) as alternative injector option

Integration of the LPA into the storage ring straight sections is being studied

The LPA injector can sustain filling the ring and top-up operation with a charge of 250 pC at 10 Hz rep rate



Conclusion

The PETRA III complex operates with an **availability of 98%**, while aging effects become more and more noticeable.



A **6-month long shutdown** is planned to start in September 2026, with the major task to refurbish PIA and the interlock system in the injector chain.

PETRA IV got accepted for the national roadmap priority list

- Evaluation for final funding approval in December 2025
- Project start 2027 – with 2.5 years of dark time in 2030-2032



Thank you for your attention

Full Coupling: new PETRA IV standard operating mode



PETRA IV brightness mode

1900 bunches 4 ns spacing 200 mA (1 nC per bunch)

standard mode: emittance 20 pm; 20% coupling (**17pm/3pm**); energy spread 0.1 %

	β_x (m)	β_y (m)	σ_x (μm)	σ_x' (μrad)	σ_y (μm)	σ_y' (μrad)
Standard straights	2.2	2.2	6.1	2.8	2.7	1.2
Long straights	4.0	4.0	8.2	2.0	3.7	0.9
Long straight north	5.0	5.0	9.1	1.8	4.1	0.8

All other optics functions are zero: $\alpha_x = \alpha_y = D_x = D_x' = D_y = D_y' = 0$

full coupling mode: emittance 20 pm; 100% coupling (**12pm/12pm**); energy spread 0.1 %

	β_x (m)	β_y (m)	σ_x (μm)	σ_x' (μrad)	σ_y (μm)	σ_y' (μrad)
Standard straights	2.2	2.2	5.1	2.3	5.1	2.3
Long straights	4.0	4.0	6.9	1.7	6.9	1.7
Long straight north	5.0	5.0	7.7	1.5	7.7	1.5

Contact

Deutsches Elektronen-
Synchrotron DESY

www.desy.de

Michaela Schaumann

MPE

Michaela.Schaumann@desy.de

0049 40 8998 1769