




ALBA Status and Upgrade

33rd ESLS workshop – 30th October 2025, Soleil

Ferran Fernandez, on behalf of the Accelerators team

2025 Operation

ALBA Synchrotron Light Source




Operation Calendar 2025





	JANUARY				FEBRUARY				MARCH				APRIL				MAY				JUNE				JULY				AUGUST				SEPTEMBER				OCTOBER				NOVEMBER				DECEMBER			
Weekday	Week Day	Shift	M	A	N	Week Day	Shift	M	A	N	Week Day	Shift	M	A	N	Week Day	Shift	M	A	N	Week Day	Shift	M	A	N	Week Day	Shift	M	A	N	Week Day	Shift	M	A	N	Week Day	Shift	M	A	N	Week Day	Shift	M	A	N			
Mo	1																																															
Tu																																																
We																																																
Th																																																
Fr																																																
Sa																																																
Su																																																
Mo	2																																															
Tu																																																
We																																																
Th																																																
Fr																																																
Sa																																																
Su																																																
Mo	3																																															
Tu																																																
We																																																
Th																																																
Fr																																																
Sa																																																
Su																																																
Mo	4																																															
Tu																																																
We																																																
Th																																																
Fr																																																
Sa																																																
Su																																																
Mo	5																																															
Tu																																																
We																																																
Th																																																
Fr																																																
Sa																																																
Su																																																
Mo	6																																															
Tu																																																
We																																																
Th																																																
Fr																																																
Sa																																																
Su																																																
Mo	7																																															
Tu																																																
We																																																
Th																																																
Fr																																																
Sa																																																
Su																																																
Mo	8																																															
Tu																																																
We																																																
Th																																																
Fr																																																
Sa																																																
Su																																																
Mo	9																																															
Tu																																																
We																																																
Th																																																
Fr																																																
Sa																																																

SR Bending
magnets PS
incident

	Hours
M	1.152
BL	4.512
Total	5.664



SR-Bending Magnets Power Converter incident



SR-Bending Magnets Power Converter incident

- SR PS tested after Winter Shutdown (1 week before start operation)
- SR PS worked during first 4 M days
- Failure the day before start with Beamlines
- Temporary solution: rent two transformers from a Belgium company (not same voltage)
- New transformers bought and installed following shutdown
- Operations calendar 2025 modified to recover the 13 BL days lost

	JANUARY			FEBRUARY			MARCH			APRIL			MAY			JUNE			JULY			AUGUST			SEPTEMBER			OCTOBER			NOVEMBER			DECEMBER		
Weekday	WeekDay	Shift	M	A	N	WeekDay	Shift	M	A	N	WeekDay	Shift	M	A	N	WeekDay	Shift	M	A	N	WeekDay	Shift	M	A	N	WeekDay	Shift	M	A	N	WeekDay	Shift	M	A	N	
Mo	1										1	EH	BL	BL	BL						27	1	EH	BL	BL	BL	28	1	EH	M	M	M				
Tu											2	EH	BL	BL	BL						2	2	EH	M	M	M										
We											3	EH	BL	BL	BL						3	3	EH	BL	BL	BL										
Th											4	EH	BL	BL	BL						4	4	EH	BL	BL	BL										
Fr											5	EH	BL	BL	BL						5	5	EH	BL	BL	BL										
Sa											6	EH	BL	BL	BL						6	6	EH	BL	BL	BL										
Su											7	EH	BL	BL	BL						7	7	EH	BL	BL	BL										
Mo	2										8	EH	BL	BL	BL						8	8	EH	BL	BL	BL										
Tu											9	EH	BL	BL	BL						9	9	EH	BL	BL	BL										
We											10	EH	BL	BL	BL						10	10	EH	BL	BL	BL										
Th											11	EH	BL	BL	BL						11	11	EH	BL	BL	BL										
Fr											12	EH	BL	BL	BL						12	12	EH	BL	BL	BL										
Sa											13	EH	BL	BL	BL						13	13	EH	BL	BL	BL										
Su											14	EH	BL	BL	BL						14	14	EH	BL	BL	BL										
Mo	3										15	EH	BL	BL	BL						15	15	EH	BL	BL	BL										
Tu											16	EH	BL	BL	BL						16	16	EH	BL	BL	BL										
We											17	EH	BL	BL	BL						17	17	EH	BL	BL	BL										
Th											18	EH	BL	BL	BL						18	18	EH	BL	BL	BL										
Fr											19	EH	BL	BL	BL						19	19	EH	BL	BL	BL										
Sa											20	EH	BL	BL	BL						20	20	EH	BL	BL	BL										
Su											21	EH	BL	BL	BL						21	21	EH	BL	BL	BL										
Mo	4										22	EH	BL	BL	BL						22	22	EH	BL	BL	BL										
Tu											23	EH	BL	BL	BL						23	23	EH	BL	BL	BL										
We											24	EH	BL	BL	BL						24	24	EH	BL	BL	BL										
Th											25	EH	BL	BL	BL						25	25	EH	BL	BL	BL										
Fr											26	EH	BL	BL	BL						26	26	EH	BL	BL	BL										
Sa											27	EH	BL	BL	BL						27	27	EH	BL	BL	BL										
Su											28	EH	BL	BL	BL						28	28	EH	BL	BL	BL										
Mo	5										29	EH	BL	BL	BL						29	29	EH	BL	BL	BL										
Tu											30	EH	BL	BL	BL						30	30	EH	BL	BL	BL										
We											31	EH	BL	BL	BL						31	31	EH	BL	BL	BL										
Th																																				
Fr																																				
Sa																																				
Su																																				
Mo																																				
Tu																																				

- 28th April 12h30 a general blackout affected the whole country (ALBA machine day)




- ALBA UPS and diesel generators worked as expected
 - Critical equipment kept running: data servers, internet, vacuum system, SCW cryocoolers, ...
 - Some equipment status secured for a safe restart
- Afternoon and night shifts cancelled. All the staff required for the recovery to meet early next morning
- The following day (beam for users) it took 8h to recover
 - Turn on transformers, power up SA racks, turn on water cooling...
- Some lessons learnt → CRISIS COMMITTEE working in procedures/checklists

ALBA Accelerator Developments

New Booster Power Supplies




- Install Easter 2026 → SAT Summer 2026
- Both present and new PS operative → switch rack



Present PS




Aluminum cooling water circuit

- Dedicated water cooling circuit for aluminum chambers cooling





3rd Order Harmonic Cavities

- Installation of 4 harmonic RF systems in ALBA SR
- Planned to be in operation by the end 2026
- 2 cavities in long straight sections: S08 & S12



Double Dipole Kicker

- Installation of DDK in ALBA SR this winter shutdown




1 Power Supply

Outer coils powered

Dipole field for on-axis injection

Useful during commissioning




2 Power Supplies

Outer + Inner coils powered

Zero field at the stored beam

Field peak at the injected beam






ALBA II Upgrade

ALBA II Objectives

- Replace the Storage ring Accelerator of ALBA
- Upgrade the existing beamlines
- Build new long beamlines

ALBA II Design Constrains

- Keep beam energy **3 GeV**
- Keep the **tunnel** → SR with similar compact circumference
- Keep **existing ID beamlines** → preserve 16 cells and source points
- Bending beamlines can be relocated
- Keep **injector** (present $\varepsilon_x^{\text{booster}} = 10 \text{ nm} \cdot \text{rad}$)
- Keep **infrastructures**, as much as possible
- **Straight sections** $\sim 4 \text{ m}$, with $\beta_x \sim \beta_y \sim 2 \text{ m}$
- Reduce **emittance** by more than a factor 10 ($< 400 \text{ pmrad}$)



ALBA II Main Dates

September 2025



Starting the design

Presenting to funding agencies the 'pre-White Paper'

ALBA II included in 2021-2024 ALBA Strategy Plan

First funding for prototyping (ALBA01) – 7.5 M€

Funding for 1st ALBA II BL (ALBA05) – 10 M€

New plots assigned for Long BLs extension - 16 M€

White Paper published

Decision on long BLs

Government approval long-term budget (2024-2038)

Define project work packages

2020 2021 2022 2023 2024 2025 2026 2027 2028 2029 2030 2031 2032 2033

Prototyping

Design


Production + Assembly

Dark period

Operation


ALBA II Lattice Design

- October 2024 5BA with octupoles (ESLS'24)




- September 2025 Alpha lattice

In this modification (inspired by M.Abo-Bakr, P.Goslawski, HZB), **all the straight sections, including the long ones, have low betas, but the injection section would be asymmetric to produce low β_x at the thin septum while high β_x at the DDK kicker**




ALBA II Correction Scheme





- ◆ 11 BPM
- ▲ 11 HCM (7 in Sext, 4 in SS)
- ▼ 11 VCM (7 in Sext, 4 in SS)
- 16 quadrupole gradients
- ★ 11 SKCOR in octupoles

ALBA II Lattice Design



- Octupoles ON only during injection? → improve lifetime



ALBA II Prototyping






Straight Section SR corrector





BPM test chamber
and buttons



ALBA II Prototyping





ALBA II Prototyping



Vacuum test bench



CuCrZr chamber



Light extraction → magnets modifications

ALBA II Implementation program

- Tunnel Removal and Installation plan
- Required spaces for storage and assembly

Install SR+FE T1

Install SR15




- Move in SR girders
- Align girders
- Open magnets
- Move in VC arc
- Align arc (BPMs)
- Close magnets

Install SR16

- Move in SR girders
- Align girders
- Open magnets
- Move in VC arc
- Align arc (BPMs)
- Close magnets

Install SR01

- Move in SR girders
- Align girders
- Open magnets
- Move in VC arc
- Align arc (BPMs)
- Close magnets



**On behalf of the Accelerator Division
and the ALBA II team,**

Thanks for your attention