

PSI

Center for Accelerator Science
and Engineering


Diagnostics for SLS2.0

DEELS 2024, Synchrotron SOLEIL


Cigdem Ozkan Loch

Electron Beam Instrumentation group

SLS → SLS 2.0



Timeline



SLS Dismantling


September 30th, 2023: SLS was switched OFF

Dismantling went according to plan

- October: Removal of all tunnel roof bars
- Removal of all cable trays and cooling distribution along Ring
- Removal of all re-used components: 3HC, Kickers, Undulators, ...
- Removal of RF modulator & Klystron and most of Electrical cabinets
- Removal of all front ends

November: Removal of all girders with magnets

December: Tunnel floor painted



Give away




- 14 sets of Bergoz BPM electronics (2 per set) [available for free...!!!](#)
- They were installed around the IDs, integrated to a position interlock signal to the MIS once the beam would extend a pre-defined position offset.

Arc vacuum chamber


18m arc assembly




Arc transport & storage frame




- Vacuum arc fits in the magnets apertures
- Installation procedure validated
- ... minor corrections of cooling pipes.




- Arc assembly and alignment at off-site assembly/storage location
- Girder pre-aligned and installed on ground plates
- Permanent magnet dipoles are on slides and pushed into place after the vacuum chamber is completed
- One arc installed every two weeks
- Most cables prepared in factory and installed in bundles (length + plug)
- Radial position of consecutive magnets within $\pm 60\mu\text{m}$
- Longitudinal position of magnets are within $\pm 500\mu\text{m}$



Then and now...



October 2023



January 2024




February 2024



April 2024

4 arcs installed
5th almost complete

Other systems



- Magnet assembly and tests proceeding in a timely fashion
 - Quadrupole Series: 112 / 112 ready
 - Steerers: 117 / 117 ready
 - Sextupoles: 194 / 270 ready
 - Octupoles: 194 / 268 ready
 - Triplet Bending magnet: 26 / 60 ready
 - Reverse Bends: 104 / 150 ready (2 per day)
- Cross talk measurements on going to check against simulation results

- All power supplies have been made, tested and are being installed into the racks
- BPMs (mechanics and electronics) are on the right track





Four cavities at PSI:

- 1 cavity already conditioned to 600 kV
- 1 cavity under conditioning in a test stand





Location of Solid state amplifiers (SSA)
500 MHz / 150 kW, 4 units
Delivery schedule is tight

Baseline systems

Inherited Devices	Purpose	Requirements	for SLS 2.0
Current Monitor (Bergoz PCT)	Storage Ring Current, Transmission Efficiency and Lifetime	0-400mA to 0.1mA	Adapt mechanically New DAQ system
Charge Monitors (Bergoz ICT)	Transfer efficiency	0-400pC to 1%	New DAQ system
Fill Pattern Monitor	Synchronization of the injection chain to refill any electron bucket, to keep desired storage ring filling pattern	Sufficient bandwidth & gain to resolve single electron buckets	Relocate New DAQ system
Streak Camera	Bunch length measurement	2ps resolution every 100ms	Relocate to new BL

New Devices	Purpose	Requirements	for SLS 2.0
Screen Monitors in BRTL	Emittance and Twiss parameter measurement from booster	< 10 μ m/pixel, higher sensitivity (< 10pC), 20mmx20mm FOV	New design New controls
Loss Monitors	Protecting and positioning beam within IDs Scraper optimization Sensitive for lifetime Low charge on-axis injection	Locating losses in BRTL and SR Turn-by-turn	New
Beam Size Monitors	Coupling and emittance measurements, stability diagnostics, energy spread	Sensitive to low currents, high dynamic range and rep rate	2 new front ends


Booster-to-Ring Transfer Line




SITF 500MHz stripline
+ SM chamber



Screen Monitor




Bastler aca4505







Scheimpflug geo.



Canon focus ring





Screen Monitor (injection straight)



- ✓ stable regarding CBI from long./transv. HOMs
- ✓ max. dissipated power: 11.1W/SiC + 1.4W on beam pipe

Impedance calculations done by Dr. A. Citterio



Storage Ring Beam Size Monitor




Horizontal emittance	Open IDs, low current	150 pm
	Closed IDs, 400mA	136 pm
	Nominal	157 pm
Vertical emittance	1-2% coupling	2-3 pm
	Nominal	10 pm
	Range of operation	8-12 pm

Vertical emittance change of 1pm $\rightarrow \sigma_y=400$ nm
 Horizontal emittance of 7pm $\rightarrow \sigma_x=250$ nm


Opening angle: 8mrad x 8mrad





Fresnel Zone Plates



ZP wafer



Central stop






- ✓ Simultaneous 2D info
- ✓ Tilt
- ✓ Very small beams
- ✓ Excellent resolution
- ✓ Fits inside tunnel walls
- ✓ In-house production




- Nominal beam size at the BM: $8.6 \times 6.8 \mu\text{m}^2$
- Vertical beam size variation: 2-28 μm
Horizontal beam size variation: 5-12 μm
- Outermost zone width is 120nm
 - due to 1st ZP demagnification $\rightarrow \sim 650\text{nm}$ at source plane
 - spatial resolution of 2nd ZP is $\sim 146\text{nm}$
 - with detector sampling of 2.5x \rightarrow sampling at electron beam size plane $\sim 260\text{nm}$

- Source point - CZP: 7500mm
 - CZP - MZP: 1748.6mm
 - MZP - detector: 1589.8mm
 - FOV at source: $35 \mu\text{m} \times 35 \mu\text{m}$
 - Effective Magnification: 5
 - Central Stop Size: 0.79mm
- } 11.8keV






Arc01/1st dipole: emittance measurement



Arc01/1st dipole: visible line




pi-polarization




Arc08/standard dipole : dispersion dominant


Opening angle: 5mrad x 8mrad





Fill Pattern Monitor




- Two options for an interleaved sampling scheme is under evaluation
 - 4GSps interleaved on 12 turns (i.e. 96S/b)
 - 6GSps interleaved on 16 turns (i.e. 192S/b)
- *FPFB is under the domain of the BPM & FB group*



Longitudinal Loss Monitor





1. Injection optimization
2. Minimization of losses
3. Observing beam drifts






- ADC: 250MHz / 16 bit / 8 inputs
- Input voltage ±1V / a DC 50Ohm
- Level-shifter circuitry module and Photomultiplier module on PAC board





Current monitor: archeological findings





Same DAQ solution as ICTs




Loss Monitors for Surveillance



Scintillator geometry






Simulations by Dr. M. Aiba





- 7 per arc
- Downstream of every undulator
- 5 in the Booster-to-Ring transfer line
- PETG housing & brass screws to avoid disturbing magnetic axis

BLMs for TbT loss detection





Simulations by Dr. M. Aiba




Dose rate monitoring

- Track accumulated dose and dose rate changes at strategic locations
- Operation in 25V bias mode
- Minimum integration time 20 seconds
- No feedbacks planned
- Change the connectors to RJ45 (thanks to S. Grulja) → temperature reading lost



Additional locations:


- downstream of collimators and in line of sight in downstream arcs
- one at reference position (last triplet of last arc)




- ✓ Motion control hardware
- ✓ Pneumatics control hardware
- ✓ DAQ system (ICT, PCT, Booster PCT)
- ✓ Screen monitors (chambers and components)
- ✓ BLMs, BLDs
- ✓ 3D printing
- ✓ Most beamline components



Forecast 2024





PSI

Center for Accelerator Science
and Engineering

A. Fazan
A. Foskolos
R. Ischebeck

A. Streun
M. Boege
J. Kallestrup
V. Schlott
S. Bettoni
M. Aiba

A. Stampfli
A. Stark
M. Baldinger
Y. El Yamani

Safety

Project Management

Alignment

Electronics hardware

Hall services

3D Mech Construction

Firmware

Controls

Cabling

Vacuum

Operations

TECH COORDINATION & LOGISTICS

Electrical installation

Cooling

IT & Network

Radiation Protection

SPS/PLC systems